

QA/QC: Virginia Experience

Tanveer Chowdhury Raja Shekharan

Asset Management Division Virginia Department of Transportation



- VDOT QA/QC Process Historical Review
- 2005 Data Collection and Processing Contract
- Control Site Evaluations
- Independent Verification & Validation
- Data Analysis
- Roadway Treatment Cost Implications
- Conclusions



VDOT QA/QC Process Historical Review

- Large infrastructure data collection contract in 2000 with ICAS
- Consensus-based windshield ratings utilized 1999-2005
- IRI QA/QC addressed 1999 2001
- Semi-automated imaging systems 1995-98
- Automated imaging/ distress contract in 2005 & 2006



VDOT QA/QC Process Historical Review

Lessons learned along the way:

- -Personnel certification training
- Validation of equipment accuracy & precision
- -Daily QC procedures
- -On-going QC process
- Independent validation & verification of results



State-of-the-practice technologies in capture and analysis of pavement data

- -Digital imaging of pavement surface
- Laser measurements of longitudinal & transverse profiles
- Automated/Semi-automated distress quantification



Data Collection and Processing Contract

569 miles of Concrete Pavements

Combination of JRCP & CRCP

2600 miles of Asphalt Pavements

~1900 miles Interstate
~700 miles ramps & loops



- Contractor had an established in-house QC/QA
- IV&V was conducted by an independent sub-contractor
- Vendor used automated and semiautomated distress identification software
- Calibrated using VDOT selected control sites
- VDOT data used as "ground truth"



Control Site Evaluations

- Establish precision & bias for
 - Roughness
 - Rutting
 - Distress
- Use to calibrate the distress rating process
 - Automated
 - Semi/Automated
 - Manual



13 Control Sites

Selected by VDOT
Various lengths
Various roughness & distresses

VDOT 10 runs
Vendor 3 to 5 runs

Control Site Evaluations

- Distress Calibrations
 - Based upon distress index values
 - Limit of +/- 10 index points from VDOT value
- Purpose
 - Training
 - Calibrate automated/semi-automated processes
 - One iteration for CRCP
 - Two iterations for JRCP
 - Three iterations for ACP
- Must complete prior to production rating



Performed after vendor in-house QC/QA process completed
10% of all production ratings reviewed
95% of deliverable must pass the IV&V review before acceptance



JRCP deliverable

- 38% of the 26 sections reviewed failed
- Feedback to vendor resulted in slight changes to their rating protocols
- New 5% sample of revised deliverable
- 100% passed the IV&V check
- Deliverable accepted



CRCP deliverable
-100% of the 29 sections reviewed passed
-Deliverable accepted



| Index Value | Original % Pass | Final % Pass |
|-------------|--------------------|--------------|
| NDR | 70.0 | 95.0 |
| LDR | 82.8 | 97.8 |

Six ACP deliverables

- Feedback to vendor resulted in changes to their rating protocols
- Entire deliverable resubmitted
- Deliverable accepted



Initial benefits of IV&V

 Increases the confidence level VDOT has in the reported data

- Provided enhanced QC/QA for vendor

- Modifications to rating protocols to suit project
- Increased QA checks prior to delivery



Data Analysis

Condition data used for the determination of -Condition state of the pavements -Recommended maintenance treatments -Zero-based budget -Selection of sections for project-level evaluations -Planning future work needs



Data Analysis

- Maintenance treatments are recommended using decision tree approach
- Distresses and distress combinations are considered at various severity levels
- Each maintenance group has an associated unit cost
- Unconstrained needs determined



Data Analysis

- Condition states determined based on critical condition index on a scale of 0-100
- Five condition states: Excellent, Good, Fair, Poor, and Very Poor
- Deficient pavement sections are those in poor and very poor condition















Treatment Types and Costs









A comprehensive QA/QC includes: – Agency participation – Vendor certification/validation – Control sites – Vendor in-house QC/QA – Independent verification & validation



IV&V in Virginia has resulted in:

- Increased accuracy in reporting existing condition indices (changes by as much as 25%)
- Increased accuracy in reporting deficient pavements by district (20 to 25% change)
- Increased accuracy in the prediction of a needs based budget (changes as much as 21%)



Without IV&V, maintenance and rehabilitation needs may be under or over estimated by 25% or more!



Thank You